BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2013-14/OW/WORK_INDENT7728

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/04/2013-14, Date: 02.07.2013

Desilting of drains and berm cutting in ward no. 11 (Kuvempunagara), Vidyaranypaura sub division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K SUDHAKAR REDDY	
				In Figures	In Words
1	836.33	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.	Cum	120.0	Rupees One Hundred Twenty Only
2	2109	Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (orhter thatn foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications	cum	95.0	Rupees Ninety Five Only
3	2945.33	Lead for disposal of debris shall be payable at Carriage rates by mechanical means with all lead and lift, loading, undloading and labour charges etc.,complete and as per the directions of the Engineer-in-charge of the work.	cum	75.0	Rupees Seventy Five Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92